



924 Calle Negocio • Unit A
San Clemente, CA 92673
Phone: (949) 366-3070 • Fax: (949) 366-3069
www.aggregatemachineryspecialist.net
1/26/22

SKID MOUNTED DEWATERING SCREEN

Eagle Dry DS712 Dewatering Screen Skid

- Two (2) 8.5 HP vibratory motors
- Heat treated motor bridge
- Huck bolted construction
- Modular polyurethane screen media and attachment system
- Rubber vibration isolation buffers
- Rubber lined discharge chute
- Sump
- Low profile design
- Skid mounted support structure

Included options

- Walkway, Handrail, and Stairs – one side
- Discharge chute – taper to 36" discharge
- Pump kit to return sump water back to sand screw
- Recirculation kit, complete with Hoses, fittings, hardware and inlet for washer feed box
- Spray Bars

Technical Specifications

- Rated up to 300 TPH concrete sand
- Two motors
- Screen weight 8,155 lbs.

PRICE:

\$172,125.00

Rental Rate:

\$ 9,000.00 per month

Unit is schedule for delivery March 15 – 30, 2022 (AMS Item 16684). If an order is placed prior to shipment, delivery to the jobsite (within the continental United States) is included. Terms subject to prior credit approval. Sales tax is additional and charged at the appropriate rate. Freight from Mesa, AZ is also additional and charged at our actual cost. Rental option may be available subject to discussion and credit approval.

Pictures Pending